

ADDENDUM NO. 3

Issued 10 November 2026
Tender NUPA/ISTP/2026/014

Wadi Sirhan Independent Sewage Treatment Plant

This Addendum incorporates the Network Operator's Table 1-3 describing the two tie-in points referred to in Volume II Clause 1.3, requires a Bidder that elects to interrupt flows at a tie-in point to obtain the Authority's acceptance of its shutdown programme, applications for which shall be made within eight (8) Working Days of the date of this Addendum, introduces a flow range for the reliability run in Volume II Clause 7.2, replaces Volume II Clauses 8.1 to 8.3, adds to Volume V Clause 31.1 a new Unavailability Event for loss of treated effluent volume, with no cure period and with no deduction during the Ramp-Up Period, and responds to clarification requests 15 to 20.

This Addendum forms part of the RFP Documents and takes precedence in accordance with Volume I Clause 3.2. Bidders shall acknowledge receipt in Form 4-A. All other terms of the RFP Documents remain unchanged.

1. RECITALS

- 1.1 This Addendum is issued under Volume I Clause 5.3 and takes precedence over Addenda Nos. 1 and 2 in accordance with Volume I Clause 3.2.
- 1.2 A reference in this Addendum to a Clause, Table or Form is to that Clause, Table or Form as amended by Addenda Nos. 1 and 2, unless otherwise stated.

2. TIE-IN POINTS AND MAINTENANCE OF FLOWS

- 2.1 Volume II Clause 1.3 is amended by adding at the end: **'The two designated tie-in points are TP-1 and TP-2, described in Table 1-3, which is reproduced at Appendix A to this Addendum as issued by the Northern Region Water Services Company (the Network Operator) and is incorporated into this Volume by reference.'**
- 2.2 Table 1-3 is issued in the Arabic language. The Arabic text governs. The English translation at Appendix B is provided for convenience only.
- 2.3 The Bidder shall elect, for each tie-in point, one of the following methods of maintaining flows during the connection works, and shall state its election in the construction methodology section of the Technical Proposal: (a) temporary over-pumping, without interruption of flow in the existing collection network; or (b) interruption of flow within the permitted shutdown window stated for that tie-in point in Table 1-3.
- 2.4 The temporary works for method (a) shall be capable of passing, at each tie-in point, the maximum transfer flow stated for that tie-in point in Table 1-3.
- 2.5 Where the Bidder elects method (b) for a tie-in point, it shall submit with Envelope A a letter from the Network Operator accepting the Bidder's proposed shutdown programme for that tie-in point (a Shutdown Acceptance Letter). Applications for a Shutdown Acceptance Letter shall be made to the Network Operator not later than eight (8) Working Days before the Proposal Due Date. The Network Operator has undertaken to respond within five (5) Working Days of receipt of a complete application.
- 2.6 A Bidder that elects method (b) for a tie-in point but does not submit a Shutdown Acceptance Letter for that tie-in point with Envelope A shall be deemed to have elected method (a) for that tie-in point.
- 2.7 A Proposal that provides for an interruption of flow at a tie-in point for longer than the maximum shutdown duration stated for that tie-in point in Table 1-3 shall be rejected.

3. RELIABILITY RUN

- 3.1 In Volume II Clause 7.2, ‘at not less than 90% of nominal capacity’ is deleted and **‘at a daily average flow, measured at the inlet works, of not less than 85% and not more than 110% of nominal capacity’** is substituted.
- 3.2 A day on which the daily average flow is outside that range shall not count towards the thirty (30) days. Volume II Clause 7.3 is unchanged.

4. OPERATION, MAINTENANCE AND SPARES

- 4.1 Volume II Clauses 8.1 to 8.3 are deleted and replaced by the following:
- ‘8.1 The Project Company shall hold a spare parts inventory sufficient for eighteen (18) months of normal operation for all items with a lead time exceeding twelve (12) weeks, and shall record that inventory in the asset register required by Clause 7.4.’
- ‘8.3 The Project Company shall employ a plant manager holding a degree in chemical, civil, environmental or mechanical engineering and having not less than ten (10) years’ experience in the operation of wastewater treatment facilities, and shall maintain a minimum of two (2) certified operators on shift at all times. The plant manager proposed for the first two (2) years of operation shall be named in the Technical Proposal, and his or her curriculum vitae shall be included as an appendix to it.’
- 4.2 The Clauses of Volume II are not renumbered. Volume II Clauses 8.4 and 8.5 are unchanged.

5. UNAVAILABILITY EVENTS

- 5.1 In Volume V Clause 31.1, ‘(b) the treated effluent fails any parameter in Volume II Table 2-4, or (c) the Facility fails to deliver treated effluent to the delivery point at the required residual head.’ is deleted and **‘(b) the treated effluent fails any parameter in Volume II Table 2-4, (c) the Facility fails to deliver treated effluent to the delivery point at the required residual head, or (d) the volume of treated effluent delivered to the delivery point on any day is less than ninety per cent (90%) of the volume of sewage received at the inlet works on that day.’** is substituted.
- 5.2 In Volume V Clause 31.3, ‘No cure period applies to an event under Clause 31.1(b).’ is deleted and **‘No cure period applies to an event under Clause 31.1(b) or Clause 31.1(d).’** is substituted.

6. RESPONSES TO CLARIFICATION REQUESTS 15 TO 20

No	Bidder question	Authority response
15	Is the Network Operator owned or controlled by the Authority?	No. The Network Operator is a separate company. Its ownership has no bearing on any requirement of the RFP Documents.
16	May ozonation be used as the disinfection process?	Ozonation shall not be used as the sole means of disinfection. Disinfection shall be by chlorination with provision for dechlorination, or by ultraviolet irradiation with a validated dose, or by a combination. Volume II Clause 3.3 applies.
17	Volume V Clause 12.3 provides that the reasonable costs of the Independent Engineer are borne equally by the parties. Does this apply to the Independent Engineer's attendance at a repeated reliability run?	No. The reasonable costs of the Independent Engineer attributable to any reliability run after the first shall be borne by the Project Company. Volume V Clause 12.3 is amended accordingly.
18	If the flow delivered to the Facility by the existing collection network during the reliability run under Volume II Clause 7.2 is lower than the flow required by that Clause, for reasons outside the Project Company's control, will the Project Company be entitled to relief?	The Authority notes the question. Volume V Clause 34 applies. The Authority does not consider further amendment necessary at this stage.

No	Bidder question	Authority response
19	Volume II Clause 7.4 requires an asset register in the Authority's standard format. Will the format be issued before the Proposal Due Date?	No. The format will be issued to the Preferred Bidder. The asset register shall be maintained in the computerised maintenance management system required by Volume II Clause 8.2 and shall be submitted to the Authority before the start of the reliability run under Volume II Clause 7.2.
20	What design flow should be used for the temporary works needed to maintain flows at the tie-in points referred to in Volume II Clause 1.3?	The temporary works shall be capable of passing the maximum transfer flow stated for each tie-in point in Table 1-3 at Appendix A to this Addendum. Section 2.4 of this Addendum applies.

FICTIONAL — ASSESSMENT PACK

APPENDIX A — TABLE 1-3 (ARABIC)

The following table is reproduced as issued by the Network Operator under cover of its letter No. 312/2026 dated 5 November 2026. The Arabic text governs in accordance with Section 2.2 of this Addendum.

Northern Region Water Services Company

شركة خدمات المياه بالمنطقة الشمالية

التاريخ: ٥ نوفمبر ٢٠٢٦ م

الرقم: ٣١٢/٢٠٢٦

الموضوع: نقاط الربط بشبكة التجميع القائمة لمحطة معالجة مياه الصرف الصحي المستقلة بوادي السرحان
مناقصة رقم: NUPA/ISTP/2026/014

جدول ٣-١: نقاط الربط وشروط إيقاف التدفق

تُحدد نقاط الربط بشبكة التجميع القائمة وشروط إيقاف التدفق فيها على النحو الآتي:

نقطة الربط	الموقع	قطر الخط القائم (مم)	فترة الإيقاف المسموح بها	أقصى مدة للإيقاف (ساعة)	مهلة الإشعار المسبق
TP-1	غرفة التفتيش MH-41 على خط الطرد الشمالي	١٠٠٠	من ٢٣:٠٠ إلى ٠٥:٠٠	٦	١٠ أيام عمل
TP-2	غرفة التفتيش MH-07 على خط الانحدار الجنوبي	٨٠٠	من ٠١:٠٠ إلى ٠٥:٠٠	٤	١٠ أيام عمل

ملاحظات:

١. لا يُسمح بأي إيقاف خلال شهر رمضان المبارك أو خلال إجازتي عيد الفطر وعيد الأضحى.
٢. يُسمح بإيقاف واحد فقط لكل نقطة ربط طوال مدة الإنشاء.
٣. تُقدّم طلبات الإيقاف عبر البوابة الإلكترونية للشركة، مرفقاً بها برنامج الإيقاف المقترح وخطة الطوارئ.
٤. جميع الأوقات المذكورة بتوقيت الرياض.

مدير إدارة تشغيل الشبكات

FICTIONAL DOCUMENT - Lamar Holding internal assessment pack - not a real tender.

End of reproduction.

APPENDIX B — ENGLISH TRANSLATION OF TABLE 1-3

This translation is provided for convenience only. The Arabic text of Table 1-3 at Appendix A governs. Network Operator's letter No. 312/2026 dated 5 November 2026. Subject: tie-in points with the existing collection network for the Wadi Sirhan Independent Sewage Treatment Plant. Tender No. NUPA/ISTP/2026/014.

Table 1-3 — Tie-in points and conditions for interruption of flow

Tie-in point	Location	Existing sewer diameter (mm)	Permitted shutdown window	Maximum shutdown duration (hours)	Advance notice
TP-1	Manhole MH-41 on the northern rising main	1,000	23:00 to 05:00	6	10 Working Days
TP-2	Manhole MH-07 on the southern gravity sewer	800	01:00 to 05:00	6	10 Working Days

Notes to Table 1-3:

- (1) No shutdown is permitted during the holy month of Ramadan.
- (2) Only one shutdown is permitted at each tie-in point during the construction period.
- (3) Shutdown requests shall be submitted through the Network Operator's electronic portal, accompanied by the proposed shutdown programme and a contingency plan.
- (4) All times are Riyadh time.

Signed: Director, Network Operations, Northern Region Water Services Company (signature and company stamp).